



Project Brief:

Project: Post delivery Scopes

Location: Samsung Shipyard in South Korea - transit to Angola

Duration: 3 Deployments – approximately 6 weeks each

► Team: 1 x Project Manager, 1 x Project Engineer, 1 x Supervisor,

1 x Team Leader, 11 x Structural/Pipe Fitters, 11 x Welders,

1 x NDT Inspector, 4 x Scaffolders, 6 x Fire Watchers, 2 x Painters,m2 x Electrical Supervisor, 4 x Electricians, 9 x


Electrical Assistants





Supply

- Prefabrication done in Dubai, Cape Town, and Walvis Bay
- Prefabricated structures/piping shipped to South Korea, Singapore, Namibia and Angola
- ► Tools and Scaffolding supplied in DNV 2.7-1 container
- ► Gas cylinders supplied in DNV 2.7-1 racks





For more details please contact: info@3cmetalme.com





Scope of Work

- Detailed survey in Shipyard and in Singapore including Laser Scanning
- Engineering including ABS review
- Prefabrication under supervision of an ABS surveyor.
- Installation onboard during
- Installation Man Hours in 2013: 35,412


Onsite Installation

- ► HP Piping (up to 15,000 PSI rated): Cement Test Line (from Cement Unit to Drill Floor), Coil Tubing line (from Cement Unit to Pipe Deck), Swagelok tubing (6,900 PSI rated)
- ▶ LP Piping: Mud Sieving system, Foam Firefighting in the Shaker Room, 3rd Party utilities (Air and Water supply lines), Potable Water line in Stainless Steel





- ▶ Structural scopes: 3 x Removable structures, 20 m3 Diesel Tank in Sack Store, 3 x Removable Spooler Bridges AFT Drill Floor, XT Reeler Frame on the Xmas Tree Carrier, Hose Hangers and Crossovers, Clamped Padeyes on the mast
- ► Electrical scopes: 3rd Party (Distribution Panel in Switchboard Room), CCTV system, Telephones, Load Cell indicator, Equipment connection
- ▶ Thermal insulation and Ducting Line installation for AC unit
- ► Zero Discharge system installation for TWMA Equipment (Engineering, Skids for equipment, Piping and Electrical)



For more details please contact: info@3cmetalme.com