

# Client: Seadrill West Gemini & Halliburton Baroid Surface Solutions


# **Project Brief**

Project: Design , Fabrication & installation of the Halliburton Zero Discharge Package

Location: Offshore AngolaDuration: 90 days on-board

3,700 Man-days (44,400 Man Hours)

▶ Team: Up to 40 Pax – Supervisor, Team leaders, Welders, Fitters, Electricians, Riggers, NDT and Painters




#### **Engineering**

- Onsite survey off shore Angola
- ► Technical expertise provided for Piping and Structure
- Electrical Expertise
- ► Complete Calculation Note and Deck analysis
- ▶ 3D drawings of the complete Installation
- Single Line Drawings & 3D pipe modelling for various projects
- Complete As-built package

## **Supply**

- Worldwide Sourcing & Prefabrication:
  - LP pipes & fittings Supply from South Africa .
  - ► Electrical cables and components from Singapore , UK and South Africa .
  - Supply and prefabrication of Structures and various platforms from Namibia & SA.
  - Tools and Equipment from SA.
  - Scaffolding supplied in DNV 2.7-1 container from SA.



For more details please contact: info@3cmetalme.com





#### **Logistics & Project Management:**

- Personnel Deployment, Logistics & co-ordination for:
  - Deployment Offshore Angola
- ► All Structures and Low Pressure Pipes road freighted from Cape Town (SA) and Walvis Bay (Namibia) to Luanda, Angola
- ▶ All Electrical cables and components have been air freighted and sea freighted from Singapore , UK and SA .
- Certification of team: Seamen's Book, Yellow Fever, BOSIET / HUFT

### **Zero Discharge Scopes of Work:**

- Supply , Prefabrication and installation :
  - Structural Skids for the TCC Module &10 x HCB's Dry Powder Silos in the Riser Bay
  - ► Halliburton Workshop, Lab and Store platforms and associated Walkways in the Casing Bay
  - Structural Skids for the 10 x HCB Wet Cutting Silos in the Cutting Skips Area and BOP area
  - 2 x Compressor Platforms below the Riser Catwalk
  - Full interface connection between Halliburton System and the Rig System. Utility lines all diameters / Slop water treatment unit connection to the Rig System
  - Over board lines dump lines: 12" and 4"
  - Additional overboard platform to accommodate 2 x Cutting Skips
  - Integration of a 6M3 Fuel Tank to the Rig System
  - Emergency Shut Down System integration on various Halliburton equipment
  - Electrical connections including PA /GA , Fire & Gas , Fibre Optic & Telephone

#### **Class Interface:**

- ABS Certification of all relevant technical documentation.
- ABS Inspection / Witness during pre-fabrication.







